PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

To:

Assistant Commissioner for Patents
United States Patent and Trademark Office
Box PCT
Washington, D.C.20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 14 September 2000 (14.09.00)	
International application No. PCT/US99/28434	**Applicant's or agent's file reference** 248/091
International filing date (day/month/year) 01 December 1999 (01.12.99)	**Priority date** (day/month/year) 15 December 1998 (15.12.98)
Applicant SHRIM, Yaron et al	

1. The designated Office is hereby notified of its election made:

[X] in the demand filed with the International Preliminary Examining Authority on:

06 July 2000 (06.07.00)

[ ] in a notice effecting later election filed with the International Bureau on:

2. The election [X] was

[ ] was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO **34, chemin des Colombettes** **1211 Geneva 20, Switzerland**	Authorized officer Kiwa Mpay
Facsimile No.: (41-22) 740.14.35	Telephone No.: (41-22) 338.83.38

PATENT COOPERATION TREATY

From the
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY

To: MARK A. CATAN
LYON & LYON LLP
633 WEST FIFTH STREET
SUITE 4700
LOS ANGELES CA 90071-2066

PCT

NOTIFICATION OF TRANSMITTAL OF INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Rule 71.1)

OV file
Cc M.Ca

Date of Mailing *(day/month/year)*	24 APR 2001
Applicant's or agent's file reference 248/091 WO	IMPORTANT NOTIFICATION

International application No.	International filing date *(day/month/year)*	Priority Date *(day/month/year)*
PCT/US99/28434	01 DECEMBER 1999	15 DECEMBER 1998

Applicant
ELECTRIC FUEL LIMITED

1. The applicant is hereby notified that this International Preliminary Examining Authority transmits herewith the international preliminary examination report and its annexes, if any, established on the international application.

2. A copy of the report and its annexes, if any, is being transmitted to the International Bureau for communication to all the elected Offices.

3. Where required by any of the elected Offices, the International Bureau will prepare an English translation of the report (but not of any annexes) and will transmit such translation to those Offices.

4. REMINDER

The applicant must enter the national phase before each elected Office by performing certain acts (filing translations and paying national fees) within 30 months from the priority date (or later in some Offices)(Article 39(1))(see also the reminder sent by the International Bureau with Form PCT/IB/301).

Where a translation of the international application must be furnished to an elected Office, that translation must contain a translation of any annexes to the international preliminary examination report. It is the applicant's responsibility to prepare and furnish such translation directly to each elected Office concerned.

For further details on the applicable time limits and requirements of the elected Offices, see Volume II of the PCT Applicant's Guide.

Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer Monique Wills Telephone No. (703) 308-0661

Form PCT/IPEA/416 (July 1992) *

PATENT COOPERATION TREATY

From the
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY

To: MARK A. CATAN
LYON & LYON LLP
633 WEST FIFTH STREET
SUITE 4700
LOS ANGELES CA 90071-2066

PCT

WRITTEN OPINION

(PCT Rule 66)

or: file
cc M. Catan

Date of Mailing *(day/month/year)*	14 FEB 2001
Applicant's or agent's file reference 248/091 LSO	REPLY DUE within TWO months from the above date of mailing 4/14/01

International application No.	International filing date *(day/month/year)*	Priority date *(day/month/year)*
PCT/US99/28434	01 DECEMBER 1999	15 DECEMBER 1998

International Patent Classification (IPC) or both national classification and IPC
IPC(7): H01M 4/00 and US Cl.: 429/77

Applicant
ELECTRIC FUEL LIMITED

1. This written opinion is the first (first, etc.) drawn by this International Preliminary Examining Authority.

2. This opinion contains indications relating to the following items:

I	[X]	Basis of the opinion
II	[ ]	Priority
III	[ ]	Non-establishment of opinion with regard to novelty, inventive step or industrial applicability
IV	[ ]	Lack of unity of invention
V	[X]	Reasoned statement under Rule 66.2(a)(ii) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
VI	[ ]	Certain documents cited
VII	[ ]	Certain defects in the international application
VIII	[ ]	Certain observations on the international application

3. The applicant is hereby invited to reply to this opinion.

When? See the time limit indicated above. ~~The applicant may, before the expiration of that time limit, request this Authority to grant an extension., see Rule 66.2(d).~~

How? By submitting a written reply, accompanied, where appropriate, by amendments, according to Rule 66.3. For the form and the language of the amendments, see Rules 66.8 and 66.9.

Also For an additional opportunity to submit amendments, see Rule 66.4.
For the examiner's obligation to consider amendments and/or arguments, see Rule 66.4 *bis*.
For an informal communication with the examiner, see Rule 66.6.

If no reply is filed, the international preliminary examination report will be established on the basis of this opinion.

4. The final date by which the international preliminary examination report must be established according to Rule 69.2 is: 15 APRIL 2001

Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231	Authorized officer MONIQUE WILLS
Facsimile No. (703) 305-3230	Telephone No. (703) 308-0661

WRITTEN OPINION

International application No.
PCT/US99/28434

I. Basis of the opinion

1. With regard to the **elements** of the international application:*

[X] the international application as originally filed

[X] the description:
pages (See Attached) , as originally filed
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

[X] the claims:
pages (See Attached) , as originally filed
pages _____ , as amended (together with any statement) under Article 19
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

[X] the drawings:
pages (See Attached) , as originally filed
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

[X] the sequence listing part of the description:
pages (See Attached) , as originally filed
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.
These elements were available or furnished to this Authority in the following language _____ which is:

[ ] the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).

[ ] the language of publication of the international application (under Rule 48.3(b)).

[ ] the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the written opinion was drawn on the basis of the sequence listing:

[ ] contained in the international application in printed form.

[ ] filed together with the international application in computer readable form.

[ ] furnished subsequently to this Authority in written form.

[ ] furnished subsequently to this Authority in computer readable form.

[ ] The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

[ ] The statement that the information recorded in computer readable form is identical to the writen sequence listing has been furnished.

4. [X] The amendments have resulted in the cancellation of:

[X] the description, pages NONE

[X] the claims, Nos. NONE

[X] the drawings, sheets/~~fig~~ NONE

5. [ ] This opinion has been drawn as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).

** Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this opinion as "originally filed".*

WRITTEN OPINION

International application No.
PCT/US99/28434

V. Reasoned statement under Rule 66.2(a)(ii) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. statement

Novelty (N)	Claims	1-35	YES
	Claims	NONE	NO
Inventive Step (IS)	Claims	NONE	YES
	Claims	1-35	NO
Industrial Applicability (IA)	Claims	1-35	YES
	Claims	NONE	NO

2. citations and explanations

Claims 1-35 an inventive step under PCT Article 33(3) as being obvious over Konishi et al. U.S. Patent 5,242,763 in view of Cheiky U.S. Patent 4,894,295.

Konishi teaches a battery pack composed of a plurality of flat type gas depolarizable galvanic cells such as the zinc-air battery system and its packaging method. The case contains holders 1c (Fig. 1A) that support the batteries inside the casing (col. 4 lines 45-55). The holders or projections are an integral part of the bottom wall of the casing and together with the remainder of the casing defining an air conduit inside the casing see Figure 2A. The casing also contains openings or ventilators (col. 4 lines 30-40) that communicate with the conduit projections of a certain value of height are formed on at least one of the outer surfaces of the positive and negative terminals of the flat type cells. The casing is made of plastic (col. 4 lines 50-55). The reference is also concerned with the battery pack having leak proof characteristics (col. 3 lines 45-55). Konishi also teaches that the assembly may be used as high capacity power sources for various portable electronic appliance.

Konishi is silent to a second series of holes in the casing remaining unobstructed for all possible normal manual holding positions of said case hand-held device-combination. The reference is also silent to the housing being made from hydrophobic surface material.

However, Cheiky teaches that it is conventional to make such casings from nylon. The reference is also concerned with maintaining a continuous air flow path to avoid inhibiting the cell's functions (col. 1 lines 40-61). The reference addresses this problem by employing two series of holes in the casing. The reference also teaches a concave base (fig. 3).

Therefore, it would have been obvious to one of ordinary skill in the art at the time the invention was made to employ the additional series of holes of Cheiky in the casing of Konishi, because the skilled artisan recognizes that the battery's energy output drops dramatically if the flow of air is inhibited or ceases for any reason. Therefore, it is desirable to provide a metal-air battery whose design enables continuous flow of air (Continued on Supplemental Sheet.)

Supplemental Box
(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: Boxes I - VIII

TIME LIMIT:

The time limit set for response to a Written Opinion may not be extended. 37 CFR 1.484(d). Any response received after the expiration of the time limit set in the Written Opinion will not be considered in preparing the International Preliminary Examination Report.

I. BASIS OF OPINION:

This opinion has been drawn on the basis of the description:
page(s) 1-61, as originally filed.
page(s) NONE, filed with the demand.
and additional amendments:
NONE

This opinion has been drawn on the basis of the claims:
page(s) 1-6, as originally filed.
page(s) NONE, as amended under Article 19.
page(s) NONE, filed with the demand.
and additional amendments:
NONE

This opinion has been drawn on the basis of the drawings:
page(s) 1/22 -22/22, as originally filed.
page(s) NONE, filed with the demand.
and additional amendments:
NONE

This opinion has been drawn on the basis of the sequence listing part of the description:
page(s) NONE, as originally filed.
pages(s) NONE, filed with the demand.
and additional amendments:
NONE

V. 2. REASONED STATEMENTS - CITATIONS AND EXPLANATIONS (Continued):
across the air cathode membrane.

Regarding the hydrophobic material, Cheiky teaches that it is conventional to fabricate metal-air casings from nylon which is a hydrophibic material.

---------- NEW CITATIONS ----------
US 4,894,295A (CHEIKY) 16 JANUARY 1990, see column 1, lines 50-68.
US 5,242,763A (KONISHI et al) 7 SEPTEMBER 1993, see column 3, lines 40-60.

PATENT COOPERATION TREATY

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference 248/091	FOR FURTHER ACTION	See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
International application No. PCT/US99/28434	International filing date *(day/month/year)* 01 DECEMBER 1999	Priority date *(day/month/year)* 15 DECEMBER 1998
International Patent Classification (IPC) or national classification and IPC IPC(7): H01M 4/00 and US Cl.: 429/77		
Applicant ELECTRIC FUEL LIMITED		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.

2. This REPORT consists of a total of 7 sheets.

   ☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority. (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

   These annexes consist of a total of 0 sheets.

3. This report contains indications relating to the following items:

   - I ☒ Basis of the report
   - II ☐ Priority
   - III ☐ Non-establishment of report with regard to novelty, inventive step or industrial applicability
   - IV ☐ Lack of unity of invention
   - V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
   - VI ☐ Certain documents cited
   - VII ☐ Certain defects in the international application
   - VIII ☐ Certain observations on the international application

Date of submission of the demand	Date of completion of this report
06 JULY 2000	09 APRIL 2001
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer Monique Wills Telephone No. (703) 308-0661

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/US99/28434

I. Basis of the report

1. With regard to the **elements** of the international application:*

[X] the international application as originally filed

[X] the description:
pages (See Attached) , as originally filed
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

[X] the claims:
pages (See Attached) , as originally filed
pages _____ , as amended (together with any statement) under Article 19
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

[X] the drawings:
pages (See Attached) , as originally filed
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

[X] the sequence listing part of the description:
pages (See Attached) , as originally filed
pages _____ , filed with the demand
pages _____ , filed with the letter of _____

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.
These elements were available or furnished to this Authority in the following language _____ which is:

[ ] the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).

[ ] the language of publication of the international application (under Rule 48.3(b)).

[ ] the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

[ ] contained in the international application in printed form.

[ ] filed together with the international application in computer readable form.

[ ] furnished subsequently to this Authority in written form.

[ ] furnished subsequently to this Authority in computer readable form.

[ ] The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

[ ] The statement that the information recorded in computer readable form is identical to the writen sequence listing has been furnished.

4. [X] The amendments have resulted in the cancellation of:

[X] the description, pages NONE

[X] the claims, Nos. NONE

[X] the drawings, sheets/~~fig~~ NONE

5. [ ] This report has been drawn as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).**

** Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).*

***Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.*

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/US99/28434

V. Reasoned statement under Article 35(2) with regard t novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. statement

Novelty (N)	Claims	1-35	YES
	Claims	NONE	NO
Inventive Step (IS)	Claims	NONE	YES
	Claims	1-35	NO
Industrial Applicability (IA)	Claims	1-35	YES
	Claims	NONE	NO

2. citations and explanations (Rule 70.7)

Claims 1-35 an inventive step under PCT Article 33(3) as being obvious over Konishi et al. U.S. Patent 5,242,763 in view of Cheiky U.S. Patent 4,894,295.

Konishi teaches a battery pack composed of a plurality of flat type gas depolarizable galvanic cells such as the zinc-air battery system and its packaging method. The case contains holders 1c (Fig. 1A) that support the batteries inside the casing (col. 4 lines 45-55). The holders or projections are an integral part of the bottom wall of the casing and together with the remainder of the casing defining an air conduit inside the casing see Figure 2A. The casing also contains openings or ventilators (col. 4 lines 30-40) that communicate with the conduit projections of a certain value of height are formed on at least one of the outer surfaces of the positive and negative terminals of the flat type cells. The casing is made of plastic (col. 4 lines 50-55). The reference is also concerned with the battery pack having leak proof characteristics (col. 3 lines 45-55). Konishi also teaches that the assembly may be used as high capacity power sources for various portable electronic appliance.

Konishi is silent to a second series of holes in the casing remaining unobstructed for all possible normal manual holding positions of said case hand-held device-combination. The reference is also silent to the housing being made from hydrophobic surface material.

However, Cheiky teaches that it is conventional to make such casings from nylon. The reference is also concerned with maintaining a continuous air flow path to avoid inhibiting the cell's functions (col. 1 lines 40-61). The reference addresses this problem by employing two series of holes in the casing. The reference also teaches a concave base (fig. 3).

Therefore, it would have been obvious to one of ordinary skill in the art at the time the invention was made to employ the additional series of holes of Cheiky in the casing of Konishi, because the skilled artisan recognizes that the battery's energy output drops dramatically if the flow of air is inhibited or ceases for any reason. Therefore, it is desirable to provide a metal-air battery whose design enables continuous flow of air (Continued on Supplemental Sheet.)

Supplemental Box
(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: Boxes I - VIII

I. BASIS OF REPORT:

This report has been drawn on the basis of the description,
page(s) 1-61, as originally filed.
page(s) NONE, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the claims,
page(s) 1-6, as originally filed.
page(s) NONE, as amended under Article 19.
page(s) NONE, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the drawings,
page(s) 1/22 -22/22, as originally filed.
page(s) NONE, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the sequence listing part of the description:
page(s) NONE, as originally filed.
pages(s) NONE, filed with the demand.
and additional amendments:
NONE

V. 2. REASONED STATEMENTS - CITATIONS AND EXPLANATIONS (Continued):
across the air cathode membrane.

Regarding the hydrophobic material, Cheiky teaches that it is conventional to fabricate metal-air casings from nylon which is a hydrophibic material.

---------- NEW CITATIONS ----------
US 4,894,295A (CHEIKY) 16 JANUARY 1990, see column 1, lines 50-68.
US 5,242,763A (KONISHI et al) 7 SEPTEMBER 1993, see column 3, lines 40-60.

From the INTERNATIONAL SEARCHING AUTHORITY

PCT

NOTIFICATION OF TRANSMITTAL OF THE INTERNATIONAL SEARCH REPORT OR THE DECLARATION

(PCT Rule 44.1)

T :
LYON & LYON LLP
Attn. CATAN, MARK A.
633 West Fifth Street, Suite 4700
Los Angeles, California 90071-2066
UNITED STATES OF AMERICA

APR 1 1 2000

LYON & LYON INTL PROSECUTION

Date of mailing *(day/month/year)* 03/04/2000	
Applicant's or agent's file reference 248/091	**FOR FURTHER ACTION** See paragraphs 1 and 4 below
International application No. PCT/US 99/ 28434	International filing date *(day/month/year)* 01/12/1999
Applicant ELECTRIC FUEL LIMITED et al.	

1. [X] The applicant is hereby notified that the International Search Report has been established and is transmitted herewith.

Filing of amendments and statement under Article 19:
The applicant is entitled, if he so wishes, to amend the claims of the International Application (see Rule 46):

When? The time limit for filing such amendments is normally 2 months from the date of transmittal of the International Search Report; however, for more details, see the notes on the accompanying sheet.

Where? Directly to the International Bureau of WIPO
34, chemin dee Colombettes
1211 Geneva 20, Switzerland
Fascimile No.: (41-22) 740.14.35

6.3.2000

For more detailed instructions, see the notes on the accompanying sheet.

2. [ ] The applicant is hereby notified that no International Search Report will be established and that the declaration under Article 17(2)(a) to that effect is transmitted herewith.

3. [ ] **With regard to the protest** against payment of (an) additional fee(s) under Rule 40.2, the applicant is notified that:

[ ] the protest together with the decision thereon has been transmitted to the International Bureau together with the applicant's request to forward the texts of both the protest and the decision thereon to the designated Offices.

[ ] no decision has been made yet on the protest; the applicant will be notified as soon as a decision is made.

4. **Further action(s):** The applicant is reminded of the following:

Shortly after **18 months** from the priority date, the international application will be published by the International Bureau. If the applicant wishes to avoid or postpone publication, a notice of withdrawal of the international application, or of the priority claim, must reach the International Bureau as provided in Rules 90*bis*.1 and 90*bis*.3, respectively, before the completion of the technical preparations for international publication.

Within **19 months** from the priority date, a demand for international preliminary examination must be filed if the applicant wishes to postpone the entry into the national phase until 30 months from the priority date (in some Offices even later).

Within **20 months** from the priority date, the applicant must perform the prescribed acts for entry into the national phase before all designated Offices which have not been elected in the demand or in a later election within 19 months from the priority date or could not be elected because they are not bound by Chapter II.

Nam and mailing address of the International Searching Authority European Patent Office, P.B. 5818 Patentlaan 2 NL-2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	Authorized officer Maria Van der Hoeven

F rm PCT/ISA/220 (July 1998)

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's fil reference	**FOR FURTHER ACTION** see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.	
248/091		
International application No.	International filing date *(day/month/year)*	(Earliest) Priority Date *(day/month/year)*
PCT/US 99/ 28434	01/12/1999	15/12/1998

Applicant

ELECTRIC FUEL LIMITED et al.

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 3 sheets.

[X] It is also accompanied by a copy of each prior art document cited in this report.

1. **Basis of the report**

a. With regard to the **language**, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.

[ ] the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

b. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international search was carried out on the basis of the sequence listing :

[ ] contained in the international application in written form.

[ ] filed together with the international application in computer readable form.

[ ] furnished subsequently to this Authority in written form.

[ ] furnished subsequently to this Authority in computer readble form.

[ ] the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

[ ] the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. [ ] **Certain claims were found unsearchable** (See Box I).

3. [ ] **Unity of invention is lacking** (see Box II).

4. With regard to the **title**,

[X] the text is approved as submitted by the applicant.

[ ] the text has been established by this Authority to read as follows:

5. With regard to the **abstract**,

[X] the text is approved as submitted by the applicant.

[ ] the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of th **drawings** to be published with th abstract is Figure No. 34C

[X] as suggested by the applicant.

[ ] None of the figures.

[ ] because the applicant failed to suggest a figure.

[ ] because this figure better characterizes the invention.

IPC 7 H01M12/06 H01M2/10

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 H01M

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 4 547 438 A (MCARTHUR WILLIAM J ET AL., MARPLE GROVE, US) 15 October 1985 (1985-10-15) column 2, line 13 - line 16 column 2, line 46 - line 66 column 3, line 32 -column 4, line 53 column 6, line 66 -column 7, line 11 figures 1,2,9	27,28
Y		29
A		1,2,4-9, 11,12, 17,24, 31,35

-/--

[X] Further documents are listed in the continuation of box C.

[X] Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
23 March 2000	03/04/2000

Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	Peis, S

Form PCT/ISA/210 (second sheet) (July 1992)

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	PATENT ABSTRACTS OF JAPAN vol. 1997, no. 03, 31 March 1997 (1997-03-31) & JP 08 298103 A (TOSHIBA BATTERY CO LTD), 12 November 1996 (1996-11-12) abstract	29
A		27,28
A	PATENT ABSTRACTS OF JAPAN vol. 1996, no. 08, 30 August 1996 (1996-08-30) & JP 08 106895 A (MATSUSHITA ELECTRIC IND CO LTD), 23 April 1996 (1996-04-23) abstract	1,2,4-9, 11,12, 17,20, 24, 26-31,35
Y	PATENT ABSTRACTS OF JAPAN vol. 1996, no. 02, 29 February 1996 (1996-02-29) & JP 07 272704 A (JAPAN STORAGE BATTERY CO LTD), 20 October 1995 (1995-10-20) abstract	29
A		1-35
A	US 5 242 763 A (KONISHI HAJIME ET AL, NARA, JP) 7 September 1993 (1993-09-07) column 1, line 5 - line 10 column 4, line 25 -column 5, line 17 figures 1A,1B,2A,5B,6A,6B,	1-35
A	WO 96 08048 A (CENTURION INT INC., LINCOLN, US) 14 March 1996 (1996-03-14) page 1, line 28 - line 33 page 2, line 15 - line 34 page 4, line 30 -page 8, line 20 figures 12,13,17,18	1-35
A	PATENT ABSTRACTS OF JAPAN vol. 1996, no. 03, 29 March 1996 (1996-03-29) & JP 07 302623 A (MATSUSHITA ELECTRIC IND CO LTD), 14 November 1995 (1995-11-14) abstract	12,14,15

1

cited in search report		date	member(s)		date
US 4547438	A	15-10-1985	NONE		
JP 08298103	A	12-11-1996	NONE		
JP 08106895	A	23-04-1996	NONE		
JP 07272704	A	20-10-1995	NONE		
US 5242763	A	07-09-1993	JP	4366547 A	18-12-1992
WO 9608048	A	14-03-1996	AU	1733495 A	27-03-1996
JP 07302623	A	14-11-1995	NONE		

These Notes are intended to give the basic instructions concerning the filing of amendments under article 19. The Notes are based on the requirements of the Patent Cooperation Treaty, the Regulations and the Administrative Instructions under that Treaty. In case of discrepancy between these Notes and those requirements, the latter are applicable. For more detailed information, see also the PCT Applicant's Guide, a publication of WIPO.

In these Notes, "Article", "Rule", and "Section" refer to the provisions of the PCT, the PCT Regulations and the PCT Administrative Instructions respectively.

INSTRUCTIONS CONCERNING AMENDMENTS UNDER ARTICLE 19

The applicant has, after having received the international search report, one opportunity to amend the claims of the international application. It should however be emphasized that, since all parts of the international application (claims, description and drawings) may be amended during the international preliminary examination procedure, there is usually no need to file amendments of the claims under Article 19 except where, e.g. the applicant wants the latter to be published for the purposes of provisional protection or has another reason for amending the claims before international pbulication. Furthermore, it should be emphasized that provisional protection is available in some States only.

What parts of the International application may be amended?

Under Article 19, only the claims may be amended.

During the international phase, the claims may also be amended (or further amended) under Article 34 before the International Preliminary Examining Authority. The description and drawings may only be amended under Article 34 before the International Examining Authority.

Upon entry into the national phase, all parts of the international application may be amended under Article 28 or, where applicable, Article 41.

When? Within 2 months from the date of transmittal of the international search report or 16 months from the priority date, whichever time limit expires later. It should be noted, however, that the amendments will be considered as having been received on time if they are received by the International Bureau after the expiration of the applicable time limit but before the completion of the technical preparations for international publication (Rule 46.1).

Where not to file the amendments?

The amendments may only be filed with the International Bureau and not with the receiving Office or the International Searching Authority (Rule 46.2).

Where a demand for international preliminary examination has been/is filed, see below.

How? Either by cancelling one or more entire claims, by adding one or more new claims or by amending the text of one or more of the claims as filed.

A replacement sheet must be submitted for each sheet of the claims which, on account of an amendment or amendments, differs from the sheet originally filed.

All the claims appearing on a replacement sheet must be numbered in Arabic numerals. Where a claim is cancelled, no renumbering of the other claims is required. In all cases where claims are renumbered, they must be renumbered consecutively (Administrative Instructions, Section 205(b)).

The amendments must be made in the language in which the international application is to be published.

What documents must/may accompany the amendments?

Letter (Section 205(b)):

The amendments must be submitted with a letter.

The letter will not be published with the international application and the amended claims. It should not be confused with the "Statement under Article 19(1)" (see below, under "Statement under Article 19(1)").

The letter must be in English or French, at the choice of the applicant. However, if the language of the international application is English, the letter must be in English; if the language of the international application is French, the letter must be in French.

The letter must indicate the differences between the claims as filed and the claims as amended. It must, in particular, indicate, in connection with each claim appearing in the international application (it being understood that identical indications concerning several claims may be grouped), whether

(i) the claim is unchanged;

(ii) the claim is cancelled;

(iii) the claim is new;

(iv) the claim replaces one or more claims as filed;

(v) the claim is the result of the division of a claim as filed.

The following examples illustrate the manner in which amendments must be explained in the accompanying letter:

1. [Where originally there were 48 claims and after amendment of some claims there are 51]:
"Claims 1 to 29, 31, 32, 34, 35, 37 to 48 replaced by amended claims bearing the same numbers; claims 30, 33 and 36 unchanged; new claims 49 to 51 added."

2. [Where originally there were 15 claims and after amendment of all claims there are 11]:
"Claims 1 to 15 replaced by amended claims 1 to 11."

3. [Where originally there were 14 claims and the amendments consist in cancelling some claims and in adding new claims]:
"Claims 1 to 6 and 14 unchanged; claims 7 to 13 cancelled; new claims 15, 16 and 17 added." or
"Claims 7 to 13 cancelled; new claims 15, 16 and 17 added; all other claims unchanged."

4. [Where various kinds of amendments are made]:
"Claims 1-10 unchanged; claims 11 to 13, 18 and 19 cancelled; claims 14, 15 and 16 replaced by amended claim 14; claim 17 subdivided into amended claims 15, 16 and 17; new claims 20 and 21 added."

"Statement under article 19(1)" (Rule 46.4)

The amendments may be accompanied by a statement explaining the amendments and indicating any impact that such amendments might have on the description and the drawings (which cannot be amended under Article 19(1)).

The statement will be published with the international application and the amended claims.

It must be in the language in which the international appplication is to be published.

It must be brief, not exceeding 500 words if in English or if translated into English.

It should not be confused with and does not replace the letter indicating the differences between the claims as filed and as amended. It must be filed on a separate sheet and must be identified as such by a heading, preferably by using the words "Statement under Article 19(1)."

It may not contain any disparaging comments on the international search report or the relevance of citations contained in that report. Reference to citations, relevant to a given claim, contained in the international search report may be made only in connection with an amendment of that claim.

Consequence if a demand for international preliminary examination has already been filed

If, at the time of filing any amendments under Article 19, a demand for international preliminary examination has already been submitted, the applicant must preferably, at the same time of filing the amendments with the International Bureau, also file a copy of such amendments with the International Preliminary Examining Authority (see Rule 62.2(a), first sentence).

Consequence with regard to translation of the international application for entry into the national phase

The applicant's attention is drawn to the fact that, where upon entry into the national phase, a translation of the claims as amended under Article 19 may have to be furnished to the designated/elected Offices, instead of, or in addition to, the translation of the claims as filed.

For further details on the requirements of each designated/elected Office, see Volume II of the PCT Applicant's Guide.

PCT WORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification [7]: H01M 12/06, 2/10 — A1

(11) International Publication Number: WO 00/36699

(43) International Publication Date: 22 June 2000 (22.06.00)

(21) International Application Number: PCT/US99/30382

(22) International Filing Date: 20 December 1999 (20.12.99)

(30) Priority Data:
09/216,343 18 December 1998 (18.12.98) US
09/321,352 27 May 1999 (27.05.99) US

(71) Applicant: AER ENERGY RESOURCES, INC. [US/US]; 4600 Highlands Parkway, Suite G, Smyrna, GA 30082 (US).

(72) Inventors: PEDICINI, Christopher, S.; 405 Saddlebrook Drive, Roswell, GA 30075 (US). WITZIGREUTER, John, D.; 4157 Springhill Lane, Kennesaw, GA 30144 (US).

(74) Agents: YOUNG, Jeffrey, E. et al.; Jones & Askew, LLP, 2400 Monarch Tower, 3424 Peachtree Road, N.E., Atlanta, GA 30326 (US).

(81) Designated States: CA, CN, JP, European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE).

Published
With international search report.
Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.

(54) Title: AIR-MANAGING SYSTEM FOR METAL-AIR BATTERY USING RESEALABLE SEPTUM

(57) Abstract

An air-managing system for metal-air battery includes resealable septum and one or more hollow needles. The septum separates air pathway into two segments. One segment is from air cathodes of the battery to the septum and the other is from the septum to the outside air. The needles provide conduits to connect two segments. The septum re-closes its torn portion when the needles are removed. Also disclosed is a reusable air manager including a fan and such needles. The air manager can be coupled to a disposable cell pack which has a septum that can be pierced by the needles..



FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece			TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	NZ	New Zealand		
CM	Cameroon			PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

AIR-MANAGING SYSTEM FOR METAL-AIR BATTERY USING RESEALABLE SEPTUM

Cross-Reference to Related Applications

The following patent applications, all of which are incorporated herein by reference, contain related subject matter and are being filed concurrently with the present application.

"CYLINDRICAL METAL-AIR BATTERY WITH A CYLINDRICAL PERIPHERAL AIR CATHODE"(Attorney Docket 01446-0805);

"AIR MANAGER SYSTEMS FOR METAL-AIR BATTERIES UTILIZING A DIAPHRAGM OR BELLOWS" (Attorney Docket 01446-0890);

"AIR MOVER FOR A METAL-AIR BATTERY UTILIZING A VARIABLE VOLUME ENCLOSURE" (Attorney Docket 01446-1110);

"DIFFUSION CONTROLLED AIR VENT WITH AN INTERIOR FAN" (Attorney Docket 01446-0940);

"UNIFORM SHELL FOR A METAL-AIR BATTERY"(Attorney Docket 01446-1100);

"LOAD RESPONSIVE AIR DOOR FOR A METAL-AIR CELL" (Attorney Docket 01446-1130);

"GEOMETRY CHANGE DIFFUSION TUBE FOR METAL-AIR BATTERIES" (Attorney Docket 01446-1000); and

"AIR DELIVERY SYSTEM WITH VOLUME-CHANGEABLE PLENUM OF METAL-AIR BATTERY" (Attorney Docket 01446-0910).

Field of the Invention

The present invention relates generally to batteries, and more particularly relates to an air-managing system for a metal-air battery.

Description of the Related Art

Metal-air battery cells include an air permeable cathode and a metallic anode separated by an aqueous electrolyte. During discharge of a metal-air battery, such as a zinc-air battery, oxygen from the ambient air is converted at the cathode to hydroxide, zinc is oxidized at the anode by the hydroxide, and water and electrons are released to provide electrical energy. Metal-air batteries have a relatively high energy density because the cathode utilizes oxygen from ambient air as a reactant in the electrochemical reaction rather than a heavier material such as a metal or metallic composition. Metal-air battery cells are often arranged in multiple cell packs within a common housing to provide a sufficient amount of power output. The result is a relatively lightweight battery.

To operate a metal-air battery cell, it is necessary therefore to provide a supply of oxygen to the air cathodes of the cells. An air manager system is typically used to provide reactive air and to isolate the air cathodes when the cell is idle. Some prior systems open air cathodes widely to the atmosphere or use a fan system to sweep a flow of new ambient air from openings across the air cathodes to supply oxygen at a rate sufficient to achieve the desired power output. The open air cathodes or the openings are generally sealed during non-use by sealing tapes, plugs, mechanical doors, etc. because the water vapor and oxygen in the ambient air would cause the cell to flood, dry out, or discharge in some circumstances, thereby leading to a reduction in cell efficiency and lifetime. Diffusion-controlling openings have been applied to the air manager, as shown in U.S. Patent

5,691,074. However, a more strict isolation may sometimes be desired for a longer shelf life.

The above-described sealing systems such as a sealing-tape are generally designed for single use and require new sealing means such as a new tape to seal the opening again. Mechanical doors are usually durable and thereby can open and close the openings more than once. The doors typically are positioned on a battery housing case such that a disposable battery body may have door mechanisms, which may be reusable even after the battery loses its power. However, the mechanisms require expensive moving parts and they tend to leak.

Thus, there has been a need for a reusable and practical sealing system to prevent water vapor transfer and leakage current when the battery is not in use. The system should be simple and work repeatedly during a battery lifetime, and further minimize disposable parts to lower the cost and to protect the environment. Along these lines, it would be efficient not to have to dispose of an air manager when every cell pack reaches the end of its useful life. If the battery could be divided into a disposable part and a reusable part, a simple and reliable engaging means to connect two parts may be needed.

Summary of the Invention

The invention seeks to provide an improved ventilation system and an improved ventilating method for a metal-air cell or battery, which has a long shelf life and retains essentially all its original power during a period of storage.

In accordance with the invention, this object is accomplished in a metal-air power supply system having two air pathway segments separated by a self-sealable septum, and a hollow needle to puncture the septum.

The present invention, therefore, provides a ventilation system for a metal-air battery having a housing or a case for enclosing at least one metal-air cell, at least one self-sealable septum, and one or more hollow needles. The case has at least one opening that is covered with the self-sealable septum and is sealed off from a reactive gas source or the outside air. Thus, the septum divides an air pathway into two segments. The first segment from an air cathode of the cell is

enclosed in the case and terminated by the septum. The second segment to the outside air includes tubular passages of the hollow needles. When the needles penetrate the septum, the two segments are connected and the air pathway is completed to convey a reactive gas, e.g., oxygen, to the air cathode from the outside air.

The present invention provides a multi mode ventilation system for a metal-air battery with one or more openings connected to the outside air in the second segment. At least one air-moving device is disposed in the second segment such that the device may give a satisfactory air flow rate for required power. If the openings are preferably sized, leakage current of the cell may be lowered for non-use conditions when the air-moving device is off. Furthermore, the preferably sized openings prevent the cell from flooding and drying out by exchanging water vapor with the outside air. Thus, the lowest mode is for storage, a middle mode is for non-use, and the highest mode is to provide power with the air-moving device on.

The present invention further provides a power supply system having a cell pack with at least a self-sealable septum and an air-managing device with one or more hollow needles. The cell pack may be stored alone to maintain the original power. The air-managing device engages with the cell pack when the power supply is needed.

The present invention further provides an electric device with an air-managing device and a disposable cell pack with a self-sealable septum. The air-managing device is combined in the electric device such that the consumers may only have to buy a disposable cell pack.

The present invention further provides a cell pack including one or more metal-air cells in a housing which has air opening sealed by resealable septum.

The present invention further provides a reusable ventilation system that engages with an above-mentioned cell pack. The ventilation system has one or more hollow needles, at least one air moving device or fan, and one or more openings for air ingress and egress.

Other features and advantages of the present invention will become apparent upon reviewing the following description of preferred embodiments of the invention, when taken in conjunction with the drawings and the appended claims.

Brief Description of the Drawing

FIG. 1 is a diagrammatic top view of the cell pack case and the hollow needle embodying the present invention showing position of the cells, the opening, the septum, and the hollow needle, indicating the movement direction of the needle to engage the case.

FIG. 2 is a vertical cross sectional view taken along line 2--2 of FIG.1, showing the needle ready to pierce the septum the case.

FIG. 3 is a vertical cross sectional view of the cell pack case engaged by the hollow needle.

FIG. 4 is a diagrammatic perspective view of a second embodiment of the present invention showing a cell pack including a septum positioned adjacent to an air manager equipped with hollow needles.

FIG. 5 is a vertical cross sectional view taken along line 5--5 of FIG.4.

FIG. 6 is a diagrammatic top view of a cell pack adjacent to an air manager of a third embodiment of the present invention.

FIG. 7 is a diagrammatic top view of a cell pack incorporating an air-moving device, and adjacent to a puncturing device of a fourth embodiment of the present invention.

FIG. 8 is a diagrammatic top view of a cell pack and an air-moving device contained in an electric device according to a fifth embodiment of the present.

FIG. 9 is a perspective view of a metal-air battery or a power supply according to a sixth embodiment of the present invention.

FIG. 10 is a vertical cross sectional view taken along line 10--10 of FIG.9.

FIG. 11 is a vertical cross sectional view taken along line 11--11 of FIG.9.

Description of the Preferred Embodiment

Referring now in more detail to the drawings, in which like numerals refer to like parts throughout the several views, FIGS 1, 2, and 3 show one embodiment of the present invention. This embodiment is suitable for continuous operation of the cells to provide power and to provide sufficient oxygen to generate the power without a fan. The metal-air battery includes a plurality of cells 10 enclosed within a cell case 12. Since the present invention applies to primary and secondary metal-air cells, the cells of the first embodiment and the following embodiments are similar to those disclosed and known. Suitable components for primary metal-air cells are described in U.S. Patents 5,721,065. Secondary cells also can be used with or without an air mover embodying the present invention, such as that described in U.S. Patent 5,569,551. All types of metal-air cells may benefit by use of the present invention. The figures are exaggerated for illustration. Although the use of the invention with a zinc-air battery is disclosed, this invention should be understood as being applicable to other types of metal-air battery cells. The present invention can be used with primary or secondary batteries.

The case 12 isolates the plurality of cells 10 from the outside air and defines an opening 14 that is covered with a self-sealable septum 16. The cells 10 are generally arranged such that a reactant air plenum 18 is positioned under the cells 10. The air plenum 18 generally defines an air pathway to air cathodes of the cells 10. The septum 16 is affixed at a lower portion of the case 12 and terminates the air pathway at the opening 14. A cell pack 20 includes the cells 10, the plenum 18, the case 12, and the septum 16. The cell pack 20 does not have any air vents.

A hollow needle 22 is positioned so as to puncture the septum 16. The needle 22 may be supported by a board, a case, or the like such that reciprocal longitudinal motion of the needle is enabled. The needle 22 has a needle tip 24, a longitudinal tubular passage 26, and a circular cylindrical wall defining the passage.

The needle 22 is preferably aligned perpendicular to the septum 16 so that a longitudinal motion of the needle 22 toward the septum 16 allows the needle tip 24 to pierce a portion 28 of the septum 16 and the septum material to surround tightly outside of the needle wall for sealing (FIG. 3). Part of the length of the needle 22 is inserted through the septum 16 and the needle is held by the septum material around the needle 22. Thus, the longitudinal tubular passage 26 provides an air pathway to the outside air.

By a longitudinal reverse motion of the inserted needle 22 (FIG. 3), the needle 22 is removed and the septum 16 re-closes and reseals the torn portion 28 to seal off the cell pack 20 from the outside air. This mechanism is similar to that of a vaccine bottle septum from which an inserted hypodermic needle is removed. The needle 22 may be repeatedly re-inserted through the septum 16 and removed from the septum 16 again.

The cell pack 20 may be stored before use or when the cells 10 are inactive. Because the cells 10 are not exposed to fresh air and because leakage current may be minimized, they tend to have a longer shelf life than any cell enclosed by a housing with air vents. When the cell pack 20 is in use or when the cells 10 are active, the hollow needle 22 punctures the septum 16 and the longitudinal tubular passage 26 provides an air pathway to the outside air as described before. Thus, the cells 10 supply enough current to power a load. The present invention, therefore, enables the cells to have a long shelf life and to supply enough power from time to time without using any complicated mechanical doors or any single-use tapes.

The longitudinal tubular passage or hollow portion 26 of the needle 22 is sized to satisfy a load power requirement for oxygen while it limits an air flow rate from the outside air. Thus, the tubular passage diameter may be constructed to allow the air flow. If the needle 22 is too thin, the tubular passage may allow too little air flow. If the needle 22 is too big, it may not be easy for the septum 16 to re-close the tubular passage. If the length is shorter than 1/8", it is difficult for the needle to puncture the septum 16 and/or the tube may not be able to limit the air

flow rate to a desired maximum. If the length is longer than 1/2", it is difficult to handle the needle 22 and to puncture the septum 16 with the needle 22.

Any number of the longitudinal tubular passages 26, that is, any number of needles can be used to satisfy power requirement though FIG.1 shows single needle. Two or more needles may be preferable because one or more inlet and outlet tubular passages may be supplied. By way of example, if the same power as mentioned above is required for the cell pack 20 with two needles, each needle may have a tubular passage from 0.05 to 0.25 square inches in cross-sectional area and from 0.2 to 0.5 inches in length.

The case material is mechanically self-supporting and may be plastic, metal, ceramics, or another generally gas-impermeable material. Some gas permeability through a plastic housing can be tolerated. Materials inert to acid or base may be preferable since most electrolytes are acid or base. The septum 16 is typically made of rubber, a synthetic elastomer, or known compounds that give self-resealing characteristics to the septum 16. Suitable septum material includes that used to protect medicines in vials, such as silicone, PTFE/silicone, natural rubber, butyl rubber, PTFE/natural rubber, PTFE/butyl rubber, fluorocarbon rubber, Viton® etc. These materials are usually gas-impermeable, or hardly have permeability to water, which makes the cell pack well isolated from the outside air or any other reactive gas source and gives it a long shelf life. Further, low permeability prevents a high or low concentration of water vapor in the outside air from flooding or drying out the cells 10.

However, if it is preferable to have a high initial open cell voltage and to prevent consumers from finding that a new cell pack shows a very low voltage, a semi-permeable material may be employed. The semi-permeable material can pass oxygen or a reactive gas so as to keep an open cell voltage of the cells 10 high enough for immediate use. The septum material in this case is typically chosen from silicone rubber or resin, and other oxygen semi-permeable materials.

By way of example, if a typical silicone rubber that has an oxygen permeability coefficient of 19685 (cm^3-mm/m^2 day atm) is used for the cell pack 20 with an open area of 6 cm^2, and if the required leakage current is about 1 ma, then

the required oxygen flow rate is 5.47 cm^3/day at 25° Celsius. Thus, the thickness of the septum t may be given by

$$t = 19685 \times 6 \times 10^{-4} \times 0.21 / 5.47 = 0.45 \text{ (mm)}.$$

It should be understood that the above-mentioned limit of the size of the tubular passages, the opening, the septum, and the case depends on the power requirement and that the power requirement will vary depending upon the electric device to be engaged with the cell pack 20.

Another embodiment of the present invention is shown in FIGS. 4 and 5. As with the first embodiment, the battery pack 30 is suitable for continuous use while engaged by air-admitting needles. The metal-air battery includes a plurality of cells 10 enclosed within a cell case 32. The figures are exaggerated for illustration. The case 32 defines a cell pack 34 and isolates the plurality of cells 10 from the outside air with the exception of openings 36 that are covered with a self-sealable septum 38. The openings 36 on the bottom surface of the cell pack 34 are defined by grids 40 that may divide each cell 10 and be made of a case material. The grids 40 may mechanically support the septum 38. In this embodiment, there is a small reactant air plenum 42 in the cell pack 34. The septum 38 is affixed on the bottom surface of the cell pack 34 and terminates an air pathway to the outside air at the openings 36. The cell pack 34 therefore does not have any air vents on the cathode side of the separator between the air cathode and the electrolyte.

A plenum case 44 defines an air plenum box 46 and has a plurality of hollow needles 48 and openings 50. The air plenum box 46 may be positioned and serve as an air collection plenum. The hollow needles 48 having sharp needle tips 52 and longitudinal tubular passages 54 are positioned on the upper surface of the air plenum box 46. Any number of needles at any place of the upper surface may be used to satisfy the power requirement. It is preferable to have one or more needles in each opening 36.

As described in the first embodiment, the cells 10 are isolated from the outside air to have leakage current minimized and to have a long shelf life when

they are not used, inactive, or in the storage. The plenum box 46 engages with the cell pack so that the needle tips 52 pierce portions 56 of the septum 38 and that the needles 48 penetrate the septum 38 to provide air pathways to an air plenum 58 when the cell pack 34 is in use or the cells 10 are active. The total cross-sectional area of the tubular passages 54 are generally larger than that of the openings 50 so that the total air flow through the tubular passages 54 is larger than that through the openings 50. Therefore, right after the engagement, the current available from the cells 10 increases rapidly consuming a reactive gas, e.g. oxygen, in the plenum 58 and gradually decreases upon using up the stored oxygen. Finally the available current becomes constant and is determined by the air flow rate through the openings 50. Thus, the current characteristics satisfactory for an initial high power requirement of a connected electric device may be controlled by the total cross-sectional areas of the tubular passages 54 and the openings 50, and volume of the plenum 58.

If the steady current needs to be very low, the openings 50 are preferably sized such that their length, i.e., the direction through the thickness of the case 44 is greater than their width, i.e., the direction perpendicular to the thickness of the case 44 such that diffusion of air through the openings 50 may be substantially limited. By "substantially limited," it is meant that the rate of diffusion of oxygen or contaminates through the openings 50 is so slow that humidity transfer is sufficiently small and has little appreciable impact on the efficiency or lifetime of the cell 10 after the output current becomes almost constant.

As described in the first embodiment, the plenum box 46 may be disengaged from the cell pack 34 such that the needles 48 may be removed from the septum 38, which will reseal itself. Thus, the used cell pack may keep its residual power during a period of storage. Further, the septum 38 may be made of a semi-permeable material such that the initial open cell voltage will remain high enough after a long storage as mentioned above. The sizes, the number, and the materials of the case 32, the openings 36, the septum 38, the plenum box 46, the needles 48, their tubular passages 54, and the openings 50 may be preferably varied as

described in connection with the first embodiment. In particular, the needles 48 may preferably be shorter for handling without losing their functions.

In the first two embodiments, to protect the cells from flooding or drying out during times when no load is connected to the battery, the battery pack must be disengaged to reseal the septum. Another embodiment is shown in FIG. 6, which has the same cell pack 20 as shown in FIG.1. This embodiment provides a battery pack that can remain engaged with needles through a septum without being subject to flooding or drying out. The features of the cell pack 20 are the same as described in connection with the first embodiment. However, it shows an air manager 60 with an air manager case 62, two needles 70, 72, a fan 80 as an air-moving device, and two diffusion limiting tubes or isolation tubes 82, 84 connected to the outside air through a wall of the case 62.

The air manager is positioned such that the needles 70, 72 can penetrate the septum 16. The needles 70, 72 are hollow and their needle tips 86, 88 are sharp to pierce portions 90, 92 of the septum 16 as described in the first embodiment. The needles 70, 72 are positioned on the upper surface of the air manager case 62 such that the air manager may engage with the septum 16 under the cell pack 20. The air manager case 62 is essentially impermeable such that two tubular passages 94, 96 of the needles 70, 72 and the openings 82, 84 are the only pathways to the outside of the case 62. The fan 80 is positioned in the case so as to divide space inside of the case 62 into two chambers 98, 100 and make an air flow and/or pressure difference in the case such that an outlet air flow from the cells through the tubular passage 94 and an inlet air flow to the cells through the tubular passage 96 may occur. Pressurization of the chamber 100 causes air to flow through the tubular passage 96 and also out of the chamber 100 to the outside, through the tube 84. At the same time the low pressure created in the chamber 98 causes air to be drawn from the cells through the tubular passage 94, and make-up air is drawn into the chamber 98 from outside through the tube 82. The make-up air is then re-circulated between the air manager and the cells.

The sizes of the tubular passages 94, 96 are generally larger than those of the openings 82, 84 such that an air flow resistance of the tubular passages

94, 96 may be smaller than that of the openings 82, 84. Thus, more air generally moves through the tubular passages 94, 96 in the re-circulation process.

When the cell pack 20 is not engaged with the air manager, the cell case 12 and the septum 16 isolate the cells 10 such that the cells 10 have a long shelf life. When the cells 10 are in use or are active, the air manager 60 engages with the cell pack 20 with the needles 70, 72 penetrating the septum 16 to about halfway along their length. Thus, the tubular passages 94, 96 provide air pathways from the air cathodes (not shown) of the cells 10 to the chambers 98, 100 of the air manager 60. If the chambers 98, 100 are large and filled with a reactive gas and if the tubular passages 94, 96 are wide, the initial available current characteristics are similar to those described in connection with the second embodiment. Since the openings 82, 84 are diffusion limiting tubes, the cells 10 may have a long shelf life when the fan 80 is off, even when the septum remains pierced by the needles 70, 72. The tubular passages 94, 96 could alternatively be the diffusion limiting tubes in a way of isolating the cells 10.

The diffusion limiting tube may be referred to as an isolating passageway or a diffusion limiting passageway due to its isolating capability. In accordance with an example in US Patent 5,691,074, the diffusion limiting passageways function to limit the amount of oxygen that can reach air cathodes to minimize the self discharge and leakage or drain current of a metal-air cell.

The diffusion limiting passageways 82, 84 (or alternatively 94, 96) also minimize the detrimental impact of humidity on the metal-air cell, when the fan 80 is not forcing air flow through the diffusion limiting passageways 82, 84 (or alternatively 94, 96). A metal-air cell that is exposed to ambient air having a high humidity level may absorb too much water through its air electrode and fail due to a condition referred to as "flooding". Alternatively, a metal-air cell that is exposed to ambient air having a low humidity level may release too much water vapor form its electrolyte through the air electrode and fail due to a condition referred to as "drying out".

The efficiency of the isolating or diffusion limiting passageway in terms of the transfer of air and water into and out of a metal-air cell can be described

in terms of an "isolation ratio". The "isolation ratio" is the ratio of the rate of water loss or gain by a cell while its oxygen electrodes are fully exposed to the ambient air, as compared to the rate of the water loss or gain of the cell while its oxygen electrodes are isolated from the ambient air, except through one or more limited openings, that is, diffusion limiting passageways. For example, given identical metal-air cells having electrolyte solutions of approximately thirty-five percent (35%) KOH in water, an internal relative humidity of approximately fifty percent (50%), the ambient air having a relative humidity of approximately ten percent (10%), and no fan-forced circulation, the water loss from a cell having an oxygen electrode fully exposed to the ambient air should be more than 100 times greater than the water loss from a cell having an oxygen electrode that is isolated from the ambient air, except through one or more diffusion limiting passageways. In this example, an isolation ratio of more than 100 to 1 should be obtained.

More specifically, each of the diffusion limiting passageways 82, 84 (or alternatively 94, 96) preferably has a width that is generally perpendicular to the direction of flow therethrough, and a length that is generally parallel to the direction of flow therethrough. The length and the width are selected to substantially eliminate air flow and diffusion through the diffusion limiting passageways 82, 84 (or alternatively 94, 96) while the air moving device is not forcing air flow through the diffusion limiting passageways 82, 84 (or alternatively 94, 96). The length is greater than the width, and more preferably the length is greater than about twice the width. The use of larger ratios between length and width are preferred. Depending upon the nature of the metal-air cells, the ratio can be more than 200 to 1. However, the preferred ratio of length to width is about 10 to 1.

The isolating or diffusion limiting passageways 82, 84 (or alternatively 94, 96) could form a portion of the air path must take between the ambient and the oxygen electrodes. Each of the diffusion limiting passageways 82, 84 (or alternatively 94, 96) may be defined through the thickness of the case 62, but preferably they are in the form of tubes as described above.

In general, the diffusion limiting passageways may be cylindrical, and for some applications each can have a length of about 0.3 to 2.5 inches or

longer, with about 0.88 to 1.0 inches preferred, and an inside diameter of about 0.03 to 0.3 inches, with about 0.09 to 0.19 inches preferred. The total open area of each diffusion limiting passageway for such applications, measured perpendicular to the direction of flow therethrough, is therefore about 0.0007 to 0.5 square inches. In other applications, the diffusion limiting passageways each can have a length of about 0.1 to 0.3 inches or longer, with about 0.1 to 0.2 inches preferred, and an inside diameter of about 0.01 to 0.05 inches, with about 0.15 inches preferred. The preferred dimensions for a particular application will be related to the geometry of the passageways and the cathode plenums, the particular air mover utilized, and the volume or air needed to operate the cells as a desired level.

By way of example, in a preferred embodiment of a cell pack 20 designed to power a portable computer (not shown), a 6-volt battery with 6 cells 10 is used. Each cell 10 has an output of about 1 volt or slightly higher at about 1 to 4 amps. Each cell 10 has an exposed cathode area (not shown) of about 18 to 22 square inches for a total exposed cathode area of about 108 to 132 square inches. The battery therefore has a current density of about 50 to 200 ma per square inch of cathode surface. In order to satisfy this power requirement, an air flow from 33 to 200 cubic inch/min is needed.

The diffusion limiting passageways are not necessarily cylindrical, as any cross-sectional shape that provides the desired isolation is suitable. The isolating passageways need not be uniform along their length, so long as at least a portion of each diffusion limiting passageway is operative to provided the desired isolation. Further, the diffusion limiting passageways may be straight or curved along their length. In fact, a diffusion limiting passageway may be formed by a gap between spaced apart two-dimensional surfaces, so long as the air molecules must follow a sufficiently restricted path to move from the ambient air to the air cathode. Other exemplary diffusion limiting passageways and systems are disclosed in U.S. Patent No. 5,691,074 and U.S. Application No. 08/556,613, and the entire disclosure of each of those documents is incorporated herein by reference.

Referring again to FIG. 6, when the fan 80 is turned on, a relatively large amount of air flow comes from the outside of the air manager case 62 through

the opening 82, mixes with air flow coming through the tubular passage 94, and goes into the plenum 18 through the tubular passage 96 and out of the case 62 through the opening 84. Thus, the cell pack can supply a connected electric device with required power. The fan's rotational speed may be adjusted to supply the required power. The fan is operated with power from the cells 10, and is connected by leads and terminals not shown in FIG. 6.

Since the openings 82, 84 are diffusion limiting passageways, air flow through the passageways 82, 84 may be more quantitative. The passageways 82, 84 are, thereby, preferably constructed and arranged to allow a sufficient amount of air flow therethrough while the air moving device or the fan 80 is operating so that a sufficient output current, typically at least 50 ma, and preferably at least 130 ma can be obtained from the metal-air cells 10. In addition, the diffusion limiting passageways 82, 84 are preferably constructed to limit the air flow and diffusion therethrough such that the drain current that the metal-air cells are capable of providing to a load while the fan 80 is not forcing air flow through the passageways 82, 84 is smaller than the output current by a factor of about 50 or greater. Thus, when the fan 80 is off and the humidity level within the cell is relatively constant, only a very limited amount of air diffuses through the passageways. The water vapor within the cell protects the air cathodes (not shown) from exposure to oxygen. The air cathodes are sufficiently isolated from the ambient air by the water vapor such that the cells 10 have a long shelf life without sealing the passageways 82, 84 with mechanical air doors or the like. In addition, the diffusion limiting passageways 82, 84 are preferably constructed to provide the isolation ratio of more than 50 to 1.

When the air manager 60 is disengaged from the cell pack 20, the cells 10 are essentially isolated from the outside air, and the drain current can be as low as the storage modes before first use of the cell pack 20. With the help of the semi-permeable septum 16, an initial open cell voltage may be maintained. When the air manager 60 engages the cell pack 20, the openings 82, 84 may be the only air pathways to the outside air and the drain current mode with the fan off is reduced as described above. When the fan is turned on, the current to a load can be

varied between several modes adjusted by the fan speed control to satisfy the power requirement.

Since the air manager 60 may be reusable with other cell packs even after the cell pack 20 discharges its energy, it is possible to minimize disposable parts. The sizes, the number, and the materials of the case 12, the openings 14, the septum 16, the plenum 18, the air manager case 62, the needles 70,72, their tubular passages 94,96, the chambers 98, 100, the fan 80, and the openings 82, 84 may be preferably changed as described in connection with similar parts used in the earlier embodiments.

In particular, if the needles 70,72 are large such that their tubular passages 94,96 may be larger than the diffusion limiting tubes, the fan 80 may inhale more air flow from the outside. Thus, the air cathode is exposed to air including higher concentration of oxygen so that the battery may supply more energy when the fan 80 is on. On the other hand, when the fan 80 is off and the air manager 60 engages with the cell pack 20, that is, when the battery is temporarily inactive, the cells are less isolated from the ambient air that may have a high or low humidity level so that the cells 10 are more likely to fail due to a condition referred to as "flooding" or "drying out" as described before. This may be prevented, if the air manager 60 is disengaged from the cell pack 20 such that the air passageways are re-closed by the septum 16.

Another embodiment of a cell pack 110 according to the present invention is shown in FIG. 7. A cell pack case 112 encloses cells 10, a reactive air plenum (not shown), and an air manager portion including two chambers 114, 116 separated by a fan 118. An opening 120 connects the chambers 114, 116 to the plenum. An opening 122 extends across both chambers 114, 116 and is covered with a septum 124 and sealed off from the outside air. The air manager is an air-moving device having the fan 118 to make air flow and/or pressure difference between two chambers 114 and 116. Two needles 126, 128 secured to a needle board 130 are positioned so as to puncture portions 132, 134 of the septum 124. The needles 126, 128 have sharp needle tips 136, 138 and tubular passages 140, 142 as described in the other embodiments.

When the cells 10 are not in use or inactive, the needles 126, 128 are apart from the septum 124 and cell isolation is maximized as described above. If the septum 124 is made of a semi-permeable material, a satisfactory initial open cell voltage may be maintained during storage. When the cells 10 are in use or active, the needles 126, 128 penetrate the septum 124 at portions 132, 134 to provide air pathways from air cathodes (not shown) of the cells to the outside air. When the fan is turned on, the air is circulated with make-up fresh air through the tubular passages 140, 142 and the load current is adjusted by varying the fan speed to satisfy a high power requirement of a connected electric device.

If the cell pack must be well isolated when the fan is off, the tubular passages may be sized to be diffusion limiting isolation tubes as described above. When the needles 126, 128 are apart from the septum 124, the cells 10 are essentially isolated from the outside air and the drain current may be minimized to as low a mode as the storage modes existing before first use of the cell pack 110. With the help of the semi-permeable septum 124, an initial open cell voltage may be maintained. When the needles 126, 128 penetrate the septum 124 at portions 132, 134, the tubular passages 140, 142 may be the only air pathways to the outside air and the drain current mode with the fan off is reduced as described above. When the fan is turned on, the current to a load can be varied between several modes adjusted by the fan speed control to satisfy the power requirement.

In this embodiment, a small part such as the needle board 130 can start the cell pack so as to be a switch without any electrical contacts, and provide power to a battery-preinstalled electric device. The sizes, the number, and the materials of the case 112, the openings 120, 122, the septum 124, the plenum (not shown), the chambers 114, 116, the fan 118, the openings 120, 122, the needles 126, 128, their tubular passages 140, 142, and the board 130 may preferably be changed for the purposes described above.

Another embodiment is shown in FIG. 8, which includes a cell pack 150, and an air-managing head 152, mounted in an electric device 154. The cell pack 150 includes a case 156, cells 10, a reactive air plenum below the cells (not shown), and an extra plenum 158, adjacent to an opening 160 covered by a septum

162. A pair of terminals 164, 166 connected to positive and negative leads (not shown) from the cells 10 are positioned on the exterior of the case 156 facing the air-managing head 152. The case 156 isolates the cells from the outside air with the help of the septum 162 as described in the other embodiments. The extra plenum 158 may diffuse and mix fresh and residual air inside of the case 156 and supply each air cathode evenly with reactive gas, i.e., oxygen. In the alternative, the extra plenum may be omitted, in which case the needles are directed into the reactive air plenum. If the septum 162 is made of a semi-permeable material, an initial open cell voltage may be maintained during storage.

The air-managing head 152 includes a case 170, which defines an outwardly facing rectangular recess 172 for receiving the cell pack 150. Two engaging arms 174 with knobs 176 define the recess to receive and engage with a portion of the cell pack 150. Two recesses 178 on opposite exterior walls of the cell pack case 156 receive the knobs 176 with force caused by elastic bending of the arms 174 in a similar way as a ratchet mechanism. Two terminals 180, 182 are positioned on a back wall of the recess 172 to engage the terminals 164, 166, respectively. Two electrical terminals 184, 186 or hard wiring are provided on the other side of the head 152 to supply the electric device 154 with electrical power from the cell pack 150.

Two chambers 188, 190 are formed in the air-managing head 152 separated by an air mover such as a fan 192. A needle 194 extends out from the chamber 188 and a needle 196 extends out from the chamber 190. The chambers 188, 190 are connected to outside air through tubes 198, 200, respectively. The tubes 198, 200 (shown diagrammatically) preferably are diffusion limiting isolation tubes of the type described above, and the needles 194, 196 have larger openings 202, 204 designed for free air flow rather than isolation purposes.

Thus, the cell pack 150 is removably held by the air-managing head 152 coinciding with the needles 194, 196 penetrating the septum 162. The needles 194, 196 have sharp needle tips 206, 208 to pierce portions 210, 212 of the septum 162 and the tubular passages 202, 204 to provide air pathways between air cathodes (not shown) of the cells 10 and the two chambers 188, 190.

The fan 192 makes an air flow and/or pressure difference between two chambers 188 and 190, the fan 192 being disposed in-between. The openings 198, 200 communicate with the outside air or a reactive gas source such that the reactive gas, e.g., oxygen can come through one of the openings 198, 200 and one of the tubular passages or openings 202, 204 to reach the air cathodes of the cells 10, in a manner described above.

In this embodiment, the air-managing head 152 is installed in the electric device 154 such that the consumers need only buy the cell pack 150. The cell pack can be stored in completely sealed conditions with an impermeable septum 162 or an impermeable tape (not shown) can be affixed on a semi-permeable septum 162. In the latter case, retail stores may stock the cell pack 150 after removing the tape or consumers may remove the tape sometime before use, so that the cell pack has a satisfactory initial open cell voltage. The sizes, the number, and the materials of the case 156, the opening 160, the septum 162, the plenum (not shown), the extra plenum 158, the chambers 188, 190, the fan 192, the openings 198, 200, the needles 194, 196, their tubular passages 202, 204, and other parts may preferably be changed as described above.

Another embodiment is shown in FIGS. 9, 10, and 11. A cylindrical metal-air battery or power supply has an air-managing head 220 and a cell pack 222 like the embodiment shown in FIG. 6. The air-managing head 220 has a cylindrical coupling 224, an outer case 226, two openings 228, 230, and a positive terminal 232. The cell pack has a negative terminal 234, an outer case 236, and a coupling portion 238 with two positive terminals 240, two negative terminals 242, and an elongate self-sealable septum 244.

The air-managing head 220 further includes two positive terminals 246 disposed inside of the circular cylinder 224 opposite to each other, two negative terminals (not shown) disposed inside of the circular cylinder 224 in orthogonal positions to the positive terminals 246, two hollow needles 248, 250 parallel to the axial direction of the battery, two chambers 252, 254 divided by a fan 256, and a fan controller 258.

The two chambers 252, 254 are defined with a circular plate 260 and other walls, and formed in the air-managing head 220 separated by an air mover such as the fan 256. The needle 248 extends out from the chamber 252 and the needle 250 extends out from the chamber 254. The chambers 252, 254 are connected to outside air through openings 228, 230, respectively. The openings 228, 230 (shown diagrammatically) preferably are diffusion limiting isolation tubes of the type described above, and the needles 248, 250 have larger openings 262, 264 designed for free air flow rather than isolation purposes.

The cell pack 222 further includes two cells having anode gels 266, anode containers 268, air cathodes 270, insulating end plates 272, 274, 276, current collectors and leads 278, 280, and an air plenum 282. The end plate 276 has a slit opening covered with the elongate septum 244. The two negative terminals 242 are connected to the anode containers 268 with leads 280. The two positive terminals 240 are connected to current collectors (not shown) of the air cathodes 270 with leads (not shown). These four terminals are positioned on the exterior circular periphery of the coupling portion 238 so as to connect to corresponding terminals inside of the cylindrical coupling 224 of the air-managing head 220 in order to supply the fan 256 with electric power. The positive terminal 232 of the power supply is also connected to the terminals 246 with leads (not shown). The fan controller 258 also is connected to control the supply of electric current from the cell pack 222 to the fan 256. If the elongate septum 244 is made of a semi-permeable material, a satisfactory initial open cell voltage may be maintained during storage.

The cell pack 222 may be removably held by the air-managing head 220 coinciding with the needles 248, 250 penetrating the elongate septum 244. To selectively lock the cell pack 222 to the head 220, a connector (not shown) may be provided, such as the knobs and recesses of the previous embodiment. The needles 248, 250 have sharp needle tips 284, 286 to pierce portions 288, 290 of the septum 244, and the tubular passages 262, 264 provide air pathways from air cathodes 270 of the cells to the two chambers 252, 254.

The fan 256 makes an air flow and/or pressure difference between two chambers 252 and 254. The openings 228, 230 communicate with the outside air such that oxygen can come through one of the openings 228, 230 and one of the tubular passages 262, 264 to reach the air cathodes 270 of the cells, in a manner described above.

In this embodiment, the air-managing head 220 is separable for re-use such that the consumers need only buy the cell pack 222. The cell pack can be stored in completely sealed conditions with an impermeable septum 244 or an impermeable tape (not shown) can be affixed on a semi-permeable septum 244. In the latter case, retail stores may stock the cell pack 222 after removing the tape or consumers may remove the tape sometime before use, so that the cell pack has a satisfactory initial open cell voltage. The sizes, the number, and the materials of the case 236, the septum 244, the plenum 282, the chambers 252, 254, the fan 256, the openings 228, 230, the needles 248, 250, their tubular passages 262, 264, and other parts may preferably be changed as described above. In particular, the cylindrical coupling 224 may be formed in the same size as the outer case 226 such that the whole battery is formed in a regular battery size such as "AA".

The above description is that of preferred embodiments of the invention. Various alterations and changes can be made without departing from the spirit and broader aspects of the invention as set forth in the appended claims, which are to be interpreted in accordance with the principles of patent law, including the Doctrine of Equivalents.

Claims

What is claimed is:

1. A metal-air power supply system comprising:

an enclosure surrounding one or more metal-air cells each including an air electrode;

a structure providing a first air pathway segment within the enclosure from the air electrode to a puncturable, resealable septum comprising at least a portion of the enclosure surrounding said cell;

a hollow needle forming a portion of a second air pathway segment connected to a source of reactive gas and positioned such that said needle is capable of puncturing the septum.

2. The metal-air power supply system of claim 1 further comprising at least one diffusion limiting passageway in said second air pathway segment.

3. The metal-air power supply system of claim 2 wherein said diffusion limiting passageway is defined by said needle.

4. The metal-air power supply system of claim 2 further comprising at least one air-moving device in said air pathway.

5. The metal-air power supply system of claim 4 wherein said air-moving device is disposed between said needle and said diffusion limiting passageway.

6. The metal-air power supply system of claim 1 further comprising:

at least one inlet diffusion limiting passageway and at least one outlet diffusion limiting passageway in said second air pathway segment; and

at least one air-moving device in said air pathway.

7. The metal-air power supply system of claim 6 wherein said air-moving device is disposed between said needle and said diffusion limiting passageway.

8. The metal-air power supply system of claim 1 further comprising:

at least one diffusion limiting passageway in said second air pathway segment communicating with said hollow needle and a reactive gas source; and

at least one air-moving device in said first air pathway segment between said air electrode and said septum.

9. The metal-air power supply system of claim 8, wherein said septum comprises a membrane semi-permeable to said reactive gas.

10. The metal-air power supply system of claim 1, wherein said septum comprises a membrane semi-permeable to said reactive gas.

11. The metal-air power supply system of claim 1 further comprising at least one air-moving device between said air electrode and said septum.

12. A metal-air cell pack comprising:

a housing containing one or more metal air cellss and defining a reactive air plenum associated with air electrodes of said cells; and

a pierceable, resealable septum forming a portion of an exterior wall of said housing, said septum being connected with said plenum by an air pathway.

13. A ventilation system for metal-air cells, comprising:

an air moving device within an enclosure;

one or more ventilation openings in said enclosure allowing entry of outside air; and

one or more hollow needles extending outwardly from said enclosure.



FIG 1



FIG 2



FIG 3



FIG 4



FIG 5



FIG 6



FIG 7


154
184
186
198
200
170
152
188
190
202
192
204
180
182
172
194
196
176
206
208
176
174
174
164
166
210
212
162
158
160
178
178
10
150
10
156

FIG 8



FIG 9



FIG 11



FIG 10

INTERNATIONAL SEARCH REPORT

Intern nal Application No
PCT/US 99/30382

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 H01M12/06 H01M2/10

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 H01M

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	US 5 691 074 A (PEDICINI CHRISTOPHER S) 25 November 1997 (1997-11-25) cited in the application column 3, line 66 -column 4, line 43 figure 1	1,2,4-6, 8,12,13

☐ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
15 May 2000	22/05/2000

Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	Peis, S

Form PCT/ISA/210 (second sheet) (July 1992)

INTERNATIONAL SEARCH REPORT

Information on patent family members

Inter nal Application No
PCT/US 99/30382

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
US 5691074 A	25-11-1997	AT 189343 T	15-02-2000
		AU 7451296 A	07-05-1997
		DE 69606423 D	02-03-2000
		EP 0860032 A	26-08-1998
		JP 11508728 T	27-07-1999
		WO 9715090 A	24-04-1997
		US 5919582 A	06-07-1999